

Consolidated Response to Technical Pre-Bid Queries

Tender No. TPSODL/OT/2023-24/051

Package Name: Engineering, Supply, Erection & Commissioning of 1.1 MVA Power supply to 300 bedded District Head Quarter Hospital (DHH), Korapat at Jeypore on 33 KV on "Turnkey Contract Basis"

Sr. No.	Detailed Reference to TPSODL Technical Document. Please specify Document No / Clause No / Page No	Description as per Bid Document	Remarks - Query / Clarification	TPSODL Response
1	2	3	4	5
1	Annexure-I Schedule of Items			
2	Part-A SI No-2	WPB 160x152 (30.44KG/Mtr.),13 mtr- with base plate 300x300x12	Request to provide Technical specification for the items.	Attached Separately
3	SI No-7	Lightning Arrester (30kV,10kA) (Station Class,Class 1)		Attached Separately
4	SI No-8	Lightning Arrester (9kV,10kA) (Station Class,Class)		Attached Separately
5	SI No-29	11KV 3Cx70+1CX70 mm2 XLPE Aerial bunched Cable		As per REC standerd
6	Part-B SI No-2	High Density Polyethelene (HDPE) pipe 200mm diameter, PE 80- PN8 for laying of 33kV UG cable		Attached Separately
7	SI No-7	PVC Pipe 200 MM Dia pressure Rating PN 8.00 For Cable raising		Reputed make of relavent IS/IEC
8	Part-C SI No-15	33KV outdoor VCB 1600Amp, with indoor CR panel without PT, with outdoor CT (CTR-600-300-150/1-1A,15VA, STC		Attached Separately
9	Part-D SI No-12	1.1kV Al 1CX400 Sq.mm Un-armoured Cable A2XY-FRLSH		Attached Separately
10	SI No-17	2 Core x 16 mm2 YWY-FRLSH		Attached Separately
11	Part-E SI No-3	3Ph 4-Wire, 1A 0.2 S Class HT TV Meter, AMR Compatible HT Trivector Energy Meter with Box of DLMS Category-C		Attached Separately