

1. 3.15MVA Trailer Mounted Substation Consisting of following components will be in Bidder scope.
  - i. 33KV 3-way (2LBS+ 1VCB Motorized) RMU with Metering Unit consisting of MFM with Energy parameter (96x96)-Panel mounted meter
  - ii. 3.15MVA 33KV/11KV Transformer with OCTC
  - iii. 11KV 3 Way (2LBS+ 1VCB Motorized) RMU
  - iv. 28 feet Trailer along with Prime Mover vehicle,
  - v. 33KV 3C X 50Sq mm Copper EPR Cable – 40Meters.
  - vi. 11KV 1C X 120 Sq. mm Copper EPR Cable -160 Meters
  - vii. Cable Drum for 11KV as well as 33KV Cable
  - viii. 33KV outdoor termination Kit -02 Nos. and 11KV Outdoor Termination Kit -02 Nos separately.
2. Supply of the EPR Copper cable & cable drum is in Bidder scope. Reeling & De-reeling arrangement, accessories for this operation like motor & drive arrangement, separate trolley & vehicle will be in TPSODL Scope.
3. The Transformer is with OCTC only.
4. For special Tests mentioned in the specification it is not routine / acceptance test, it is Type test. Type test reports to be submitted along with offer.
5. Cable quantity has to be considered as per Tender Specification only.